

NOW THIS DEED OF CONSTRUCTION AGREEMENT WITNESSETH:

That the BUILDERS undertake to construct for the CLIENT

S.No	Description	Area	Rate	Total
1	G+1 With Headroom(Plastering-River Sand)	2422/sq.ft	Rs.2100/s.ft	50,86,000/-
2	Sump	8,000Ltr	Rs.25/Ltr	2,00,000/-
3	Septic Tank	10,000Ltr	Rs.18/Ltr	1,80,000/-
5	Weathering Coarse	-	-	2,20,000/-
6	Compound Wall (Without Main Gate)	-	-	3,00,000/-
WITHOUT SHOP, SOACKPITS, AND ELEVATION WALL TILES.				
				Total = Rs.59,86,000/-

1. PAYMENT SCHEDULE AND TERMS:-

That the BUILDERS undertake to construct for the CLIENT: G+1 Buildup – 2,422 sq.ft,
The building on the said plot of land more particularly described in the Schedule. Here to
and do hereby agree for a CONTRACT amount of Rs.59,86,000/- (Rupees in Fifty Nine
Lakhs Eighty Six Thousand Only)


1.2 That the CLIENT has/have to pay an Token advance of Rs.1,00,000/- at the
Date of 23-04-2024. (Total Advance Rs.,10,00,000/-)

2. MODE OF PAYMENT:-

2.1. The CLIENT further to pay the balance amount of Rs. 49,86,000/- as detailed below:

S.No	Construction Stage (On completion)	Amount
1	After Basement PCC	Rs.5,50,000/-
2	After Gf 7' brick work	Rs.4,50,000/-
3	After GF roof concrete	Rs.5,00,000/-
4	After F.Floor Column Fixing	Rs.3,50,000/-
5	After F.Floor 7' brick work	Rs.3,50,000/-
6	After F.Floor roof concrete	Rs.5,00,000/-
7	After Electrical Pipes fixing Works in Wall	Rs 4,50,000/-

K. Thiraiadasel
1st PARTY


2nd PARTY

8	After External Plastering	Rs 4,50,000/-
9	After G.F Inner plastering	Rs.2,50,000/-
10	After F.F Inner plastering	Rs 2,00,000/-
11	After Plumbing Inner Pipe line Works	Rs 2,50,000/-
12	After Floor and wall tile	Rs 3,50,000/-
13	After Plumbing Inner Fitting Works	Rs 2,00,000/-
14	After Painting work	Rs 100,000/-
15	Hand over	Rs.35,000/-
TOTAL AMOUNT PAYABLE (With Advance)		Rs.59,86,000/-

2.2. That the **CLIENT** does hereby undertake to pay the aforesaid sums as provided above on demand and without default; all payments made as per the payment schedule shall be supported by valid receipts issued by the **BUILDERS**.

2.3. The timely payment of the above total consideration amount, as per schedule prescribed above by the **CLIENT** to the **BUILDERS** shall form the essence of this contract, as any delay would hamper the completion of the construction of the flat and will also cause undue hardship to the **BUILDERS**.

2.4. The **BUILDERS** shall under no circumstances be held responsible for non-sanction of the loan to the **CLIENT** for what so ever reason. The payment of installments to the **BUILDERS** by the **CLIENT** shall not be linked with housing loan availed/to be availed by the **CLIENT**.

3. CONSTRUCTION, COMPLETION AND DELIVERY OF POSSESSION:-

3.1. Having received the consideration above stated, the **BUILDERS** agree to complete the construction of the Building and undertakes to hand over the possession of the same to the **CLIENT** within **5 to 7 months from the column Marking** obtaining the building plan approvals/sanctions along with (1) months grace period, subject to force major conditions and subject to the building work not being delayed or suspended due to unexpected or unavoidable circumstances, shortage of water and commodities like steel, cement and other building materials, civil commotion, riots, acts of God, orders of court, statutes, notification etc.

K. Thiraidasel.
1st PARTY


2nd PARTY

3.2. The **CLIENT** is entitled to take possession of the Building, after paying in full all the dues including various deposits or other payments mentioned in this agreement along with additional alteration work charges, if any, within 15 (fifteen) days from the date of receipt of communication from the **BUILDERS** intimating that the said Building is ready for use and occupation.

3.3. That the **BUILDERS** do hereby undertake to ensure handing over possession of the constructions to the **CLIENT** within 15 days after completion or after receipt of the entire payment as provided herein from the **CLIENT**, whichever is later;

3.4. The **CLIENT** shall authorize the **BUILDERS** to sign & submit all the relevant documents and records on his/ her/ their behalf before the Govt. authorities like Electricity Board, Metro Water and Sewerage Board and other authorities for obtaining due service / connection to the respective premises.

4. FIRST CHARGE:-

4.1 The **BUILDERS** shall have the first lien and charge the building on the said plot of land to be constructed by the **BUILDERS** under the terms of this Agreement until all the payments are to be made to the **BUILDERS** by the **CLIENT** under this agreement.

5. ADDITIONAL AND ALTERATION WORKS:-

5.2. That in the event of the **CLIENT** desiring to alter or modify the internal partitions, change in flooring, glazed tiles and any other extra fittings shall be only at the cost of the **CLIENT** and the **CLIENT** accept to pay the entire cost within seven days from the date of approval of his request for additional/ alteration work failing which the request stands void.

5.3. That the **CLIENT** shall not proceed with interior designing work such as wood work, electrical work, etc., before taking possession from the **BUILDERS**. However, the **BUILDERS** does not owe any responsibility/liability for any breakages or damages caused to any of the finishing works or to the structure already handed over to the **CLIENT**.

5.4 That the **CLIENT** is aware of the permissible deviations from the approved plan with regard to the proposed construction.

K. Thiruvaidasel.

1st PARTY


2nd PARTY

5.5. Bore well & Motor Fixing, Septic Tank, Weathering Tiles, RCC UG Sump, Compound wall & Main Gate, Metro Water Line, Temporary EB Charges, Main EB Board, Approval Charges and Front Elevation Wall Tiles will be charged separately.

5.6 Costs of all Additional works mentioned should be paid before the work commences.

SCHEDULE: SPECIFICATIONS:

CIVIL WORK:

Anti-termite treatment to all excavated surface before concreting.

Basement level of building will be 3' from existing soil level car parking 2 feet height from earth level and **If extra Need 1 or 2 Feet Height addition charges.**

- Top of the roof height of slab will be 10'-6" including slab thickness.
- Height of **Lintel** bottom will be 7'0" from floor level.

-Loft and cupboard will be provided in all bedroom and kitchen any one side of the wall.

- Terrace floor will be finished with **Cooling Tile** flooring.
- Kitchen **Wall Tile** Up to Ceiling Level.
- Staircase with Tiles.
- Parapet wall consist 4-1/2" thick brickwork up to a height of 3'0".
- All the Structural work will be carried out as per structural detailers from structural drawing.
- Appropriate Elevation works will be done as per design. **(any Glass Or special elements required for Elevation will be charged separately).**

JOINERY:

Main door will be **Teak wood 1st quality** frame and wooden door with brass accessories and godrej lock.

All other doors will be **Flush shutters** fixed in teak 2nd quality frame size 4"x3" thick finished with enamel paint. SS Lock and handles.

K. Thiravida sel.
1st PARTY


2nd PARTY

- Good Quality PVC Doors fixed will be provided in all Toilets.
- All windows & ventilators will be **WOODEN FRAME Or UPVC** make with Glass shutters and Safety Grills.

ELECTRICAL:

- Internal Concealed electrical conduits with metal boxes; All electrical cables will be of ISI brand; Concealed wiring(**Orbit**), phase change over switch suitable for three phase electrical supply, Circuit breakers of suitable capacity as per our load requirement.
- Heater point in all toilets will be provided
- Inverter wiring provision and AC points will be provided
- Main board fixing, All Light and Fan Fittings, Exhaust Fan and Metro Water Connections owner scope.

PLUMBING & SANITARY WORKS:

- Internal plumbing lines will be concealed with 3/4" CPVC pipes, Hot water and Cold water provisions will be made.
- Branded CP & Sanitary fittings in all Toilets and Kitchen.

BATHROOM FIXTURES:

- 1 no European / Indian water closet, **Parry ware Or Metro brand** white color
- 1 no. 2in1 wall mixer, Shower, Health faucet, etc.,
- Parry ware Ceramic Wash Basin will be provided in all the toilets and dining.

TILES/FLOORING:

- All rooms Vitrified 2'x2' floor tiles (max Rs.55-60/s.ft) with 4" skirting.
- Ceramic tiles in bathroom up to 7'-0" height, Anti-skid tiles for flooring (wall tile rs.35 to 40/s.ft)

K. Thiraidasel.

1st PARTY

[Signature]
2nd PARTY

PAINTING:

7

- Internal wall – 2 coat putty, one coat primer with 2 coats of Emulsion paint.
- Ceiling- One coat white cement, one coat primer and 2 coats Emulsion paint.
- Exterior wall – 2 coats of **Ace Emulsion** paint.

OTHERS:

- **SS Handrails** in Staircase will be provided
- **6 Month free maintenance for Plumbing and Electrical.**
- **1 Year free maintenance for Over All Building.**

MATERIAL BRAND LIST:

- Cement – **Dalmia/ Ramco /Ultratech/equivalent**
- Bricks = good quality **Chamber Bricks.**
- Sand – **M-Sand, Plastering - River Sand.**
- Steel - **Fe500/550D ISI TMT Bars I- steel/equivalent.**
- Sanitary Fittings and plumbing – **PARRYWARE / METRO.**
- Electricals- **ANCHOR** Switches, **ORBIT/** Cables.
- Paint – **Asian Paints.**
- Tiles- **Rs.55-60/s.ft ,wall tile Rs.38/s.ft (ANY BRAND)**

Using Steel Details:

Footing	- 10mm Rod X 10mm Rod
Column	- 12mm Rod X 12mm Rod – 6Nos, (Middle Column -16mm Rod - 4Nos, 12mm – 2Nos)
Rings	- 8mm Rod - 7" C/C
Roof Beam	- 12mm Rod - 5Nos
Loft	- 8mm Rod X 8mm Rod
Earth Beam	- 12 mm Rod - 3Nos & 2Nos – 10mm Rod
Roof	- Main rod - 10mm, Distribute Rod - 8mm Rod, Top Rod - 8mm Rod

K. Thiravidasel.

1st PARTY

2nd PARTY


For IRISH CONSTRUCTIONS

[Signature]
Proprietor




PRICE:

S.No.	Description	Area	Rate	Total
01	SUMP	8,000/LIT(APPORX)	RS.25/S.FT	2,00,000
02	SEPTIC TANK	10,000/LIT(APPORX)	RS.18/S.FT	1,80,000
03	Weathering Coarse	Cooling Tiles	LS	2,20,000
05	Compound Wall	Without Main Gate	LS	3,00,000
	WITHOUT SHOP, MAIN GATE, SOACKPITS, AND ELEVATION WALL TILES.			
Total Amount				Rs.9,00,000
NOTE: Extra work 60% payment at work start time and after complete balance 40%.				

WITNESSES1) 

CLIENT

K. Thirumalaseli: 23/4/24

2) 

BUILDER

For K. Thirumalaseli

 23-04-24
Proprietor